Safe Work Method Statement

Company Name:	Site Address:		Other Details:
NESSIS BUILD DEVELOP - INVEST			
Contractor:	Activity/Trade:	Carpenter	Date:

TASKS	HAZARDS & RISKS	RISK CONTROL MEASURES	WHO IS RESPONSIBLE
List the tasks required to perform the activity in sequence carried out.	What can harm you - Hazards? What can happen – Risks?	List the control measures required to eliminate or reduce the risk of injury and detail how the control measures will be put in place.	Individual/s responsible to implement the control measures identified.
Entry to Site.	Entry to unsafe areas. Movement of site personnel vehicles, plant & equipment.	Undertake NESSIS Developments site induction prior to arriving on site. Risk assessment of site conditions. Training of all employees.	All personnel associated with this task.
Unloading Equipment.	Fall from vehicle. Manual handling injuries. Being struck by equipment. Crush hands. Cuts. Slips, trips & falls.	Training employees in manual handling. Team lifting. Training employees in manual handling. The use of PPE equipment such as gloves. Unload equipment on level clear area.	All personnel associated with this task.
Setting Up.	Crush hands, cuts. Slips, trips & falls. Manual handling injuries.	Use PPE equipment. Clear rubble & access to work area. Avoid difficult terrain. Secure ramps or planks. Training employees in manual handling.	All personnel associated with this task.
Unloading of House Frames/Trusses/Timber or Materials.	Being struck by delivery trucks or crane.	Site staff to be aware of entry & set up areas of truck & cranes. Crane & truck drivers to be made aware of location of on-site personnel. Training & use of PPE equipment such as hard hats & high visibility safety vests.	All personnel associated with this task.
	Crane or lifting gear failure.	Only suitably trained personnel to operate	

		1	T
		plant & equipment. No-Go zones to be	
		established around lifting area. Plant &	
		equipment to be, registered and maintained	
		with accompanying log books, and operated	
		only by licensed personnel.	
Placing of House Frames/Trusses/Timber &	Falls & trips when carrying frames.	Ensure access path is clear and free of any	All personnel associated with this task.
Materials on Ground Floor.		debris. Ensure stacking area is clear and	
		accessible without obstruction. Team lifting or	
		mechanical lifting aid used when required.	
Erecting First Storey House Frames.	Back & shoulder injury when standing house	Training in manual handling techniques. Team	All personnel associated with this task.
	frames.	lifting when required.	
	Back injury & missing target when using	Training in manual handling techniques.	
	sledge hammer to position frames.	Personnel to be trained in the correct	
		procedure in using a sledge hammer.	
	Crushing, hit by falling objects.	Remove any loose blocking before standing	
		frames. Training in the use of PPE such as	
		hard hats. No personnel to be in a direct line	
		of path associated with a falling object.	
	Fall from a step ladder when connecting	Training in the correct use of ladders. Ensure	
	frame junctions.	ladders a set up on a clear, flat & level	
		surface.	
	Injury from the use of nail guns.	Use of PPE equipment such as safety glasses	
		and gloves. Training in the use of nail guns.	
DIIII D. D.	ELIEL OF	Competent or supervised personnel only to	
1-51 JII 1 J • 1 J	- V - I () - • .	use nail guns.	
	Electrocution.	Testing, tagging & register of all power tool	
		equipment done quarterly. Training in the	
		correct use of all power tool equipment, and	
		equipment to be used by competent	
		personnel only.	
	Sun burn.	Wide brim hats, long sleeve clothing &	
		sunscreen to be used.	
Laying of First Floor Joists.	Slips, trips & falls when carrying materials.	Ensure access path is clear and free of any	All personnel associated with this task.
, ,	, , , , , , , , , , , , , , , , , , , ,	debris. Ensure stacking area is clear and	r
		accessible without obstruction. Team lifting or	
		mechanical lifting aid used when required.	
	Falling from heights.	Training in the correct use of ladders. Ensure	
		ladders a set up on a clear, flat & level	
		surface. If required, the use of a scaffold is to	
		be implemented to allow for safe work	
		practices.	
	Injury from the use of nail guns.	Training in the use of PPE equipment such as	
		in the ase of the equipment sacinas	

	1	T	
		safety glasses and gloves. Training in the use	
		of nail guns. Competent or supervised	
		personnel only to use nail guns.	
	Electrocution.	Testing, tagging & register of all power tool	
		equipment done quarterly. Training in the	
		correct use of all power tool equipment, and	
		equipment to be used by competent	
		personnel only.	
Laying of First Storey Sheet Flooring.	Slips, trips & falls when carrying materials.	Ensure access path is clear and free of any	All personnel associated with this task.
		debris. Ensure stacking area is clear and	
		accessible without obstruction. Team lifting or	
		mechanical lifting aid used when required.	
	Personnel hit by sheet flooring mishaps.	Ensure correct lifting & carrying techniques	
		are used at all times. Training in general	
λ,		lifting, carrying & handling techniques of	
		sheet flooring.	
	Back & shoulder injury when handling sheet	Training in manual handling techniques. Team	
	flooring.	lifting when required. Mechanical lifting aids	
		to be used if required.	
	Falling from heights.	Training in the use of portable ladders. Erect	
		temporary handrails if required. Erect	
		temporary work platform or scaffold if	
		required. Lay sheet flooring from one corner	
DI III D. D.	-1/-100	of floor area and work off.	
$H \subset H \cap $	Electrocution.	Testing, tagging & register of all power tool	
		equipment done quarterly. Training in the	
		correct use of all power tool equipment, and	
		equipment to be used by competent	
		personnel only.	
	Damage & injury to eyes & hands from fumes	Training in the use of PPE equipment such as	
	and usage of flooring glue.	safety glasses and gloves.	
	Injury from the use of nail guns.	Training in the use of PPE equipment such as	
	, ,	safety glasses and gloves. Training in the use	
		of nail guns. Competent or supervised	
		personnel only to use nail guns.	
Installation of First Storey Wall Frames.	Slips, trips & falls when accessing first storey	Ensure fall protection at floor perimeter &	All personnel associated with this task.
	work area.	stair void is in place & all ground floor	r
		temporary bracing is adequate. Implement	
		safe ladder access to first floor ensuring that	
		ladder is secure. Training in the use of ladder	
		access to the first storey.	
	Slips, trips, back & shoulder injuries when	Assess path prior and clear of any debris.	
	anpo, anpo, sack a shoulder injuries when	. 100000 patri prior ana olear or any aebrio.	

	lifting wall frames.	Adjust edge protection to provide sufficient	
		access to allow frames to be passed up to first	
		storey, ensuring edge protection safety is not	
		compromised. Assess weight prior to lifting	
		and use team lifting or mechanical lifting aids	
		where required.	
	Falling from heights.	Training in the use of portable ladders. Erect	
		temporary handrails if required. Erect	
		temporary work platform or scaffold if	
		required.	
	Electrocution.	Testing, tagging & register of all power tool	
		equipment done quarterly. Training in the	
		correct use of all power tool equipment, and	
		equipment to be used by competent	
		personnel only.	
	Injury from the use of nail guns.	Training in the use of PPE equipment such as	
	myan y monn and add on man game.	safety glasses and gloves. Training in the use	
		of nail guns. Competent or supervised	
		personnel only to use nail guns.	
	Fall from a step ladder when connecting	Training in the correct use of ladders. Ensure	
	frame junctions.	ladders a set up on a clear, flat & level	
	Traine junetions.	surface. Erect temporary work platform or	
		scaffold if required.	
Loading and Installation of Trusses or Roof	Wall frames falling over when loading trusses.	Ensure all framing sections, nail plates and	All personnel associated with this task.
Members.	wait frames failing over when fodding trasses.	brace strapping are nailed off before loading	All personner associated with this task.
Wichibers.	_ <i>V L L U I</i>	materials. Check that all temporary bracing is	
		adequate, as well as additional bracing	
		needed for temporary stacking of members.	
	Falls through stair voids.	Installation of stair void cover or sufficient	
	Tans through stair voids.	hand railing to be in place before access	
		gained.	
	Manual handling injuries.	Access weight of materials and use team	
	ivianda nanding injunes.	lifting or mechanical lifting aids if required.	
		Training in the use of manual handling	
		techniques.	
	Personnel hit by falling objects.	Training in the use of PPE equipment such as	
	Tersormer file by failing objects.	hard hats and safety vests.	
	Slips & trips.	Access and work area to be kept clear of	
	Jiipa & tiipa.	debris.	
	Falling from heights.	Scaffolding to be implemented if required for	
	Talling Holli Heights.	fall protection. Personnel must not walk on	
		·	
		top plates or trusses at any time. Trusses to	

		be stockpiled by crane onto top plates, which	
		have been additionally braced to support	
		extra temporary load of materials. Work	
		should be planed so that trusses/rafters are	
		arranged in sequence to minimise handling	
		during erection.	
	Personnel hit by materials when being loaded	Only competent trained and licensed	
	by crane. Crane failure.	personnel to operate plant & equipment.	
		Training in the use of PPE equipment such as	
		hard hats & safety vests. No-Go zones to be	
		established around lifting area of crane.	
	Falls, slips, trips, strains & structural frame	Ensure first truss is adequately secured as per	And the second s
	collapse.	engineers specification as a minimum, and is	
	conupse.	braced and plumbed safely. Perform all works	
		from a safely utilised ladder or scaffold	
		structure as required. Ensure working	
		conditions are safe to proceed i.e. Excessive	
		wind and wet weather at a safe minimum.	
		Ensure all ties, noggins, trimmings & tie	
		downs, as per engineers & manufacturers	
		installation specifications are adopted	
		throughout construction.	
	Cuts, crush hands.	Training in the use of PPE equipment such as	
	cuts, crush nanus.		
	Electrocution.	gloves. Testing, tagging & register of all power tool	
DUILL	Electrocution.	equipment done quarterly. Training in the	
		correct use of all power tool equipment, and	
		equipment to be used by competent	
		personnel only.	A11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Packing Up, Cleaning Up.	Falls, cuts, manual handling injuries from	Remove work platforms and extra bracing in	All personnel associated with this task.
	dismantling work platforms & extra bracing.	the reverse order that they were erected.	
		Work from adequately required ladders set	
		up as per training techniques.	
	Sunburn, eye & ear damage.	Training in the use of PPE such as safety	
		glasses, hearing protection and sunscreen and	
		long sleeve clothing.	
	Dust inhalation from sweeping up.	Training in the use of PPE such as dust masks.	
	Personnel hit by vehicle & plant movement	Ensure driver is aware of personnel on site,	
	around site.	use vehicle spotter to aid driver vision.	

• I have read and understood the content of this Safe Work Method Statement (SWMS), have inducted and trained my employees and contractors in its implementation, and all agree to work in accordance with it.

Approved by:	Company Position:	Signature:	Date:

BUILD DEVELOP INVEST

Worker Name:	Worker Signature:	Worker Name:	Worker Signature:

INTESSIS BUILD DEVELOP INVEST